

Proton Plan
Proton Projections
Accelerator Division Review
August 2005

Eric Prebys

- Projection Procedure
- Status of 2005 projections
- Revisions for future
- Long term projections
- Conclusions

- Assume traditional operational priority:
 - Protons for pBar production
 - Limited by ability to slip stack
 - Limited by max cooling rate
 - Protons for NuMI
 - Limited by max Booster batch size
 - Limited by max MI cycle rate
 - Limited by max MI proton capacity
 - (will be) limited by ability to slip stack NuMI protons in MI
 - Protons for BNB (currently MiniBooNE)
 - Determined by difference between Booster capacity and maximum MI loading.
 - Currently limited by Booster losses, and will continue to be for some time.
 - Ultimately limited by Booster rep. rate.
 - *Extremely* sensitive to fluctuations in total Booster output

- Calculate effect of various improvements based on increased acceptance:
- Use:

$$A = \delta A + \sqrt{\frac{\beta_T \epsilon_{\max}}{\beta \gamma} + \left(D \frac{\Delta p}{p} \right)^2} \Rightarrow \epsilon_{\max} = \frac{\beta \gamma}{\beta_T} \left((A - \delta A)^2 - \left(D \frac{\Delta p}{p} \right)^2 \right)$$

Effective aperture
reduction


Improvement	Date	δA_x (mm)	$\beta_{x,\max}$ (m)	$D_{x,\max}$ (m)	δA_y (mm)	$\beta_{y,\max}$ (m)	ϵ_x (π -mm- mr)	ϵ_x (π -mm- mr)	Rel. total	Incr.
Initial	---	10	45.8	6.2	4	24	15.0	15.0	85.3%	
Dogleg 3 Fix	10/03	10	40.8	4.5	4	24	17.6	15.0	100.0%	17.3%
Dogleg 13 Fix	10/04	10	36.1	3.8	4	24	20.2	15.0	114.6%	14.6%
Booster Dump Relocation	12/05	10	34.9	3.5	4	24	21.0	15.0	119.1%	4.0%
ORBUMP/400 MeV upgrade	12/05	5	34.9	3.5	4	24	29.5	15.0	167.8%	40.9%
Correctors (dipoles)	10/07	2	34.9	3.5	2	24	35.4	18.3	245.6%	46.3%

- Increased transmission once Long 13 is removed
 - 3%
 - Probably conservative
- Effect of sparse sextupole correctors on emittance
 - ~10%
 - Does not yet include significantly improved harmonic corrections
- Effect of Booster RF improvements
 - ~5% increased uptime
- Effect of Linac Low Level RF
 - ~5% improvement on average beam intensity

- History has shown that the lab tends to overestimate the benefits of particular improvements.
 - Tuning and optimization take a long time
 - Tend to asymptotically approach the goal, then get distracted by other things.
- So we...
 - Evaluate the potential of particular improvements based on effective aperture increase or uncontrolled beam loss reduction:
 - For example, if something reduces uncontrolled loss by 10%, it has the potential to allow us to send 10% more beam.
 - Consider the following scenarios:
 - "Design": After *one year* of tuning, we realize *half* of the potential benefit.
 - "Fallback": After *one year* of tuning, we realize *one quarter* of the potential benefit.

Date	"Design" Limit (1E16 p/hr)	"Fallback" Limit (1E16 p/hr)	Comment
1/2006	10.7	9.3	Effect of collimators, dogleg fix, plus some alignment
1/2007	13.6	10.6	Alignment, ORBUMP, and L13
1/2008	18.9	13.0	New corrector system

Booster Beam Limit



- These are "peak" numbers
- An "average to peak" correction is applied to get average values

- Phases of Operation

- Phase I

- After 2004 shutdown (now)
 - Lattice problems ameliorated
 - Booster limited to 7.5Hz total repetition rate
 - Ramp up to 2+5 Main Injector operation

- Phase II

- After 2005 shutdown
 - Booster capable of ~9Hz operations
 - MI still running in 2+5 mode
 - Increase beam to BNB



- Phase III

- Slip stacked (2+9) operation to NuMI
 - Possibly requires RF upgrade
 - Beam to BNB as allowed by increase Proton Source capacity

- Linear ramp-up to see benefit of improvements
- Slip stacking efficiency
- Annual shutdowns (assume 2 mo/yr)
- Uptimes: based on 2004
- Peak to average corrections
 - For BNB, based on MiniBooNE 2004
 - For NuMI, used reasonable guess
- Effects of shot setup
- Implemented as VB routines in Excel spreadsheet
 - Easy to modify




- Total Booster output:
 - Compare actual to projections from Nov., 2004 Proton Plan document
- Individual NuMI/MiniBooNE:
 - Compare actual to revised NuMI ramp/up from ~2/05
 - Note:
 - No allowance for NuMI target problems
 - No correction for pBar slip stacking problems
 - Good for MiniBooNE
 - Bad for NuMI




NuMI Target Failure

Average Protons/Hour to NuMI




Almost caught up

FY05 Integrated Beam to NuMI




Benefited
from NuMI's
problems

Average Protons/Hour to MiniBoone




FY05 Integrated Beam to MiniBoone




- Things we did well on:
 - Average total proton rate
 - More or less on track
 - NuMI load per batch
 - Predicted: $\sim 1.5E13$
 - Actual: $\sim 2.1E13$
- Things we've missed on
 - Batch intensity
 - Assumed $5E12$ based on 2004
 - Actual $\sim 4E12$
 - Largely tuning philosophy
 - Main Injector cycle rate
 - Assumed we'd be locked to 2 second rep rate by now
 - Slip stacking performance
 - Good for NuMI so far
 - Bad long term

- More realistic batch intensity
 - Before: $5.0E12 \rightarrow 5.5E12$ (peak) over next three years
 - Now: $4.5E12 \rightarrow 5.25E12$ over next five years
- Assume lower slip stacking performance
 - Before: slip stack at 90% of peak batch intensity
 - Now: slip stack at 80% of peak batch intensity (i.e., we'll achieve $9 \times 4E12$ per cycle to NuMI)
- However
 - Now assume NuMI running during shot setup
 - Effects of Linac LLRF and Booster RF on efficiency

Booster Repetition Rate





Main Injector Load



	Booster Batch Size	Main Injector Load	Cycle Time	MI Intensity	Booster Rate*	Total Proton Rate	Annual Rate at end of Phase	
		(AP + NuMI)	(sec)	(protons)	(Hz)	(p/hr)	NuMI	BNB
Actual Operation								
July, 04	5.0E+12	1+0	2.0	0.5E+13	5.3	0.7E+17	0	3.3E+20
Proton Plan								
Phase I	4.7E+12	2+1→2+5	2.0	3.3E+13	7.3	1.1E+17	2.2E+20	2.1E+20
Phase II	4.9E+12	2+5	2.0	3.4E+13	8.7	1.4E+17	2.3E+20	3.5E+20
Phase III	5.3E+12	2+9	2.2	5.8E+13	9.0	1.9E+17	3.3E+20	2.8E+20

Peak values

Averages



- Note: these projections do *not* take into account the collider turning off in 2009
 - NuMI rates would go up at least 20%
 - Possibly much higher with Stage II improvements

- The initial proton estimates have been reasonably good for 2005 so far
 - First accurate proton delivery projections ever.
- Many things went right this year:
 - Beam coggng
 - Initial NuMI multibatch operation
 - Simultaneous NuMI/MiniBooNE running
- We have revised estimates for future running
 - Reasonably confident in our estimates for NuMI, *if* slip stacking works.
 - Large inherent uncertainty in estimate for 8 GeV line